



HAL
open science

Galactic reddening in 3D from stellar photometry – an improved map

Gregory Green, Edward Schlafly, Douglas Finkbeiner, Hans-Walter Rix, Nicolas Martin, William Burgett, Peter Draper, Heather Flewelling, Klaus Hodapp, Nicholas Kaiser, et al.

► **To cite this version:**

Gregory Green, Edward Schlafly, Douglas Finkbeiner, Hans-Walter Rix, Nicolas Martin, et al.. Galactic reddening in 3D from stellar photometry – an improved map. Monthly Notices of the Royal Astronomical Society, 2018, 478 (1), pp.651-666. 10.1093/mnras/sty1008 . hal-03154963

HAL Id: hal-03154963

<https://hal.science/hal-03154963>

Submitted on 1 Mar 2021

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Galactic reddening in 3D from stellar photometry – an improved map

Gregory M. Green,^{1★†} Edward F. Schlafly,^{2‡} Douglas Finkbeiner,³ Hans-Walter Rix,⁴ Nicolas Martin,^{4,5} William Burgett,⁶ Peter W. Draper,⁷ Heather Flewelling,⁸ Klaus Hodapp,⁸ Nicholas Kaiser,⁸ Rolf-Peter Kudritzki,⁸ Eugene A. Magnier,⁸ Nigel Metcalfe,⁷ John L. Tonry,⁸ Richard Wainscoat⁸ and Christopher Waters⁸

¹Kavli Institute for Particle Astrophysics and Cosmology, Physics and Astrophysics Building, 452 Lomita Mall, Stanford, CA 94305, USA

²Lawrence Berkeley National Laboratory, One Cyclotron Road, Berkeley, CA 94720, USA

³Harvard Astronomy, Harvard-Smithsonian Center for Astrophysics, 60 Garden St., Cambridge, MA 02138, USA

⁴Max-Planck-Institut für Astronomie, Königstuhl 17, D-69117 Heidelberg, Germany

⁵Université de Strasbourg, CNRS, Observatoire astronomique de Strasbourg, UMR 7550, F-67000 Strasbourg, France

⁶GMTO Corporation, 465 N. Halstead Street, Suite 250, Pasadena, CA 91107, USA

⁷Durham University, Department of Physics, Science Laboratories, South Road, Durham DH1 3LE, UK

⁸University of Hawaii, Institute for Astronomy, 2680 Woodlawn Dr., Honolulu, HI 96822, USA

Accepted 2018 April 10. Received 2018 April 5; in original form 2017 September 6

ABSTRACT

We present a new 3D map of interstellar dust reddening, covering three quarters of the sky (declinations of $\delta \gtrsim -30^\circ$) out to a distance of several kiloparsecs. The map is based on high-quality stellar photometry of 800 million stars from Pan-STARRS 1 and 2MASS. We divide the sky into sightlines containing a few hundred stars each, and then infer stellar distances and types, along with the line-of-sight dust distribution. Our new map incorporates a more accurate average extinction law and an additional 1.5 yr of Pan-STARRS 1 data, tracing dust to greater extinctions and at higher angular resolutions than our previous map. Out of the plane of the Galaxy, our map agrees well with 2D reddening maps derived from far-infrared dust emission. After accounting for a 25 per cent difference in scale, we find a mean scatter of ~ 10 per cent between our map and the Planck far-infrared emission-based dust map, out to a depth of 0.8 mag in $E(g_{P1} - r_{P1})$, with the level of agreement varying over the sky. Our map can be downloaded at <http://argonaut.skymaps.info>, or from the Harvard Dataverse (Green 2017).

Key words: dust, extinction – ISM: structure – Galaxy: structure.

1 INTRODUCTION

Interstellar dust provides foregrounds for a wide range of astrophysical observations. At ultraviolet (UV), optical and near-infrared (NIR) wavelengths, scattering and absorption by dust grains can cause significant, or even complete, extinction. Because this scattering and absorption is wavelength-dependent, dust both dims and reddens background sources. Any UV, optical or NIR observation that relies either on a precise magnitude calibration, such as measurements of the SNe Ia redshift–luminosity distance relation, or on a precise colour calibration requires an accurate accounting for the effects of dust extinction. At longer wavelengths, in the far-infrared (FIR) and sub-millimetre regions of the spectrum, ~ 20 K

dust radiates strongly. For cosmic microwave background (CMB) cosmology, foreground dust emission must be disentangled from the background cosmological signal. Finally, at frequencies of 30–300 GHz ($\lambda \approx 1$ –10 mm) polarized dust emission is a dominant foreground in searches for B-mode polarization in the CMB. Thus, over a wide swath of the electromagnetic spectrum, dust extinction and emission pose significant challenges.

Yet dust is not only a nuisance, but is itself an important component of the structure of our Milky Way Galaxy. Dust traces the interstellar medium, and provides one means of exploring the structure and dynamics of the Galaxy. Dust also plays a critical role in the chemical dynamics of the interstellar medium, depleting it of some elements and catalysing the formation of molecular hydrogen. Dust also plays an important role in star formation, while providing us with a means of tracing star-forming regions of the Galaxy.

Until recently, the standard dust maps in use have traced the distribution of dust only in two dimensions – that is, with Galactic

* E-mail: gregreen@stanford.edu

† Porat Fellow

‡ Hubble Fellow

latitude and longitude, neglecting the distribution of dust with distance. Burstein & Heiles (1978a,b, 1982, hereafter **BH**) developed the first modern map of dust reddening across most of the sky, using column density and galaxy counts as proxies for dust reddening. In the past two decades, Schlegel, Finkbeiner & Davis (1998, hereafter **SFD**) has been a standard reference for Galactic reddening. **SFD** fitted a model of dust temperature and optical depth to IRAS 100 μm and DIRBE 100 μm and 240 μm all-sky maps, and then calibrated optical depth at 100 μm to dust reddening using a sample of elliptical galaxies with well-determined reddenings. Schlafly & Finkbeiner (2011, hereafter **SF11**) recalibrated this relation using the blue tip of the stellar locus. The Planck Collaboration (2014, hereafter **Planck14**) applied a similar method as **SFD** to far-infrared Planck and IRAS maps.

In the past decade, work has progressed on mapping dust in 3D. Marshall et al. (2006) computed a three-dimensional map of dust reddening, using post-main sequence stars observed by the Two Micron All-Sky Survey (Skrutskie et al. 2006, 2MASS) as tracers of the dust. Berry et al. (2012) used maximum-likelihood estimates of stellar reddening and distance, based on the Sloan Digital Sky Survey (York et al. 2000, SDSS) photometry, to trace dust reddening in three dimensions.

More recently, work has turned towards probabilistic methods that infer stellar properties and the distribution of dust in a self-consistent Bayesian framework. Sale et al. (2014, hereafter **Sale14**) map extinction across the northern Galactic plane, applying a hierarchical model of stellar parameters and line-of-sight dust reddening to photometry from the INT Photometric $H\alpha$ Survey of the Northern Galactic Plane (Drew et al. 2005, IPHAS). Chen et al. (2014) use optical photometry from the Xuyi Schmidt Telescope Photometric Survey of the Galactic Anticentre (XSTPS-GAC), NIR photometry from 2MASS and MIR photometry from the Wide-field Infrared Survey Explorer (Wright et al. 2010, WISE) to produce a 3D map of reddening towards the Galactic anticentre. Lallement et al. (2014) compute a 3D map of local interstellar reddening using stellar parallaxes and reddening estimates, with the added assumption that the density of dust is spatially smooth.

The present paper builds on the work of Green et al. (2014), which lays out a method for inferring the distribution of dust reddening in three dimensions, and Green et al. (2015, hereafter **Bayestar15**), which applies this method to Pan-STARRS 1 (Chambers et al. 2016, PS1) and 2MASS photometry to produce a 3D map of dust reddening across three quarters of the sky. Since the publication of **Bayestar15**, PS1 has completed its 5-band optical/NIR survey of three quarters of the sky, providing more homogeneous and deeper coverage than was previously available. This paper makes use of the newer PS1 photometry in order to present an updated map of dust reddening, covering the same three quarters of the sky, corresponding to $\delta \gtrsim -30^\circ$. This paper also makes use of the empirical mean reddening law found by Schlafly et al. (2016), which provides a better description of extinction of stellar light due to dust in the PS1 and 2MASS passbands than the reddening law used by **Bayestar15**. Finally, this paper adopts a somewhat different strategy for determining what angular resolution to use in different regions of the sky. We refer to the new map presented in this paper as ‘Bayestar17’.

The paper is organized as follows. Section 2 reviews our method of inferring the 3D distribution of dust reddening, and discusses changes made to our model since the publication of **Bayestar15**. Next, Section 3 describes the PS1 and 2MASS photometry that we make use of. Section 4 presents Bayestar17 and compares it with previous reddening maps. Finally, Section 5 discusses advantages and disadvantages of our mapping technique, suggests possible ex-

tensions to the method, and discusses future data sets that will be applied to 3D dust mapping.

2 METHOD

Our overall goal is to determine the dust extinction throughout the Galaxy, as a function of both angular position on the sky and distance from the Solar system. We use stars as tracers of the dust column. Interstellar dust both reddens and dims stellar light. If all stars were of a standard colour and luminosity, the task of determining the three-dimensional distribution of dust would be trivial, since it would be immediately possible to determine both the distance and foreground dust column of any star. However, stars have different intrinsic colours and luminosities. When we try to infer stellar distance and foreground dust column, we have to marginalize over the full range of possible stellar properties (e.g. masses, ages and metallicities). As a consequence, when we observe the broad-band photometry of a star, we can only probabilistically determine its distance and foreground dust column.

We group stars into small angular patches – sightlines. Based on broad-band photometric measurements of each star, we compute a probability distribution over the star’s distance and foreground dust column. Each star puts a constraint on the line-of-sight distance versus dust column relation. With hundreds of stars along a single sightline, we are able to put a strong constraint on the dust density as a function of distance. We assume that the reddening law is constant throughout the Galaxy.

The method used here largely follows that of Green et al. (2014, 2015), with changes described in Section 2.2.

2.1 Summary of method

We now explain our model in more detail. We wish to determine the dust extinction along a sightline, using broad-band photometry from stars that lie in a small angular region of the sky. In order to infer the extinction along the sightline, we must model the most important factors that go into producing the stellar photometry that we observe: the type of each star, the distance to each star, the distribution of dust along the sightline, the variation in dust column density with angle across the sightline, and the photometric uncertainties in the stellar photometry. Our variables are:

- (i) in each angular pixel j , the dust density in each distance bin k : α_{jk} , $k = 1, \dots, n_{\text{distances}}$. Dust column density is related to increase in extinction in each band by an assumed universal extinction vector, **R**;
- (ii) for each star i in an angular pixel j , the stellar type, Θ_{ji} , distance modulus, μ_{ji} , and fractional offset, δ_{ji} , from the ‘average’ reddening at an equivalent distance in the pixel.

Our model of how our data is generated is as follows.

- (i) Stellar angular positions are fixed. Split the sky up into small sightlines (labelled by j) and split each sightline into a fixed number of logarithmically spaced distance bins (labelled by k). The sightlines will be treated independently, and the following steps apply to each individual sightline j .
- (ii) For each star i , draw intrinsic stellar parameters Θ_{ji} (luminosity, metallicity) and distance modulus μ_{ji} from a smooth prior on the distribution of stars of different types throughout the Galaxy.
- (iii) Draw the line-of-sight dust density α_{jk} (i.e. dust density in each distance bin k) from a smooth prior on the distribution of

dust throughout the Galaxy. This determines the relation between distance modulus and cumulative extinction in the sightline, $\mathbf{A}_j(\mu)$.

(iv) Calculate the extinction, \mathbf{A}_{ji} , of each star i in sightline j . This is obtained from the line-of-sight extinction, $\mathbf{A}_j(\mu_{ji})$, with a fractional offset, δ_{ji} , particular to star i .

(v) The absolute magnitude, \mathbf{M}_{ji} (a vector containing one entry per passband), of star i is a deterministic function of stellar type, Θ_{ji} .

(vi) The apparent magnitude, \mathbf{m}_{ji} (also a vector), of star i is the sum of its absolute magnitude, \mathbf{M}_{ji} , distance modulus, μ_{ji} , and extinction, \mathbf{A}_{ji} , with the addition of Gaussian observational noise. The apparent magnitudes of the stars are our observed quantity.

We thus infer stellar type Θ_{ji} , stellar distance modulus μ_{ji} and line-of-sight dust density α_{jk} from the observed apparent magnitudes \mathbf{m}_{ji} , where j indexes the sightlines, i indexes the stars within each sightline, and k indexes the distance bins within each sightline. This model is shown as a directed factor graph (a type of plate diagram, and described in Dietz 2010) in Fig. 1.

In terms of probability densities, our model can be described as follows. The extinction of star i (in sightline j) is determined by μ_{ji} , δ_{ji} and $\{\alpha_{jk}\}_{\forall k}$ (i.e. dust density in all distance bins). Together with the distance modulus μ_{ji} and type Θ_{ji} of the star, one can obtain a model apparent magnitude (in each passband), \mathbf{m}_{ji} , for the star, and thus a likelihood:

$$p(\mathbf{m}_{ji} | \mu_{ji}, \Theta_{ji}, \delta_{ji}, \{\alpha_{jk}\}_{\forall k}). \quad (1)$$

We also have per-star priors on distance and stellar type, given by a smooth model of the distribution of stars throughout the Galaxy, and a prior on the offset of each star from the local reddening column:

$$p(\mu_{ji}, \Theta_{ji}, \delta_{ji} | \{\alpha_{jk}\}_{\forall k}) = p(\mu_{ji}, \Theta_{ji}) \times p(\delta_{ji} | \mu_{ji}, \{\alpha_{jk}\}_{\forall k}). \quad (2)$$

Finally, we have a lognormal prior on the dust density in each distance bin k along each sightline j , $p(\{\alpha_{jk}\}_{\forall k})$, whose mean is chosen to match a smooth model of the distribution of dust throughout the Galaxy.

The posterior on the line-of-sight reddening along one sightline j is then given by

$$p(\{\alpha_{jk}\}_{\forall k} | \{\mathbf{m}_{ji}\}_{\forall i}) = p(\{\alpha_{jk}\}_{\forall k}) \times \prod_{i=1}^{n_{\text{stars}}} p(\mathbf{m}_{ji} | \mu_{ji}, \Theta_{ji}, \delta_{ji}, \{\alpha_{jk}\}_{\forall k}) \times p(\mu_{ji}, \Theta_{ji}) p(\delta_{ji} | \mu_{ji}, \{\alpha_{jk}\}_{\forall k}). \quad (3)$$

We pre-compute the likelihood and prior terms for the individual stars, and then sample in α_{jk} . The mathematical details of the model and of our sampling method are given in Green et al. (2014, 2015).

2.2 Changes to the Bayestar15 approach

While the method used in this paper is substantially the same as that used in Bayestar15, we have introduced a number of changes.

First, we use a new extinction vector, relating dust density to the extinction in each passband. In Bayestar15, we used an extinction vector based on Fitzpatrick (1999) (calculated for PS1 passbands by SF11) and Cardelli, Clayton & Mathis (1989) (calculated for 2MASS passbands by Yuan, Liu & Xiang 2013). In this work, we make use of an extinction vector derived by comparison of spectra from the APO Galactic Evolution Experiment (Majewski et al. 2015, APOGEE) and the broad-band colours of stars (Schlafly et al.

2016, hereafter S16). As a significant fraction of APOGEE targets lie at low Galactic latitudes, the extinction vector found by S16 is more appropriate to the Galactic plane – where most of the dust lies – than that found by SF11. The S16 mean extinction vector corresponds to $R_V \approx 3.3$. In addition, S16 derives the extinction vector across optical and NIR passbands simultaneously, leading to a more consistent treatment of extinction across our full wavelength range. By modelling the colours of stars as a function of spectral type and a reddening component, S16 derives a mean dust extinction vector, and determines the principal axes in colour space along which the extinction vector varies. This is a variant of the ‘pair method’, where the dust extinction vector is determined by comparing stars of the same spectral type (and therefore the same luminosity and colour) that lie behind different amounts of dust obscuration (Trumpler 1930; for more recent examples of this technique, see SF11 and Yuan et al. 2013). The extinction vector derived by S16 has an undetermined grey component – that is, an arbitrary scalar constant can be added into the extinction vector. In addition, the overall scaling of the extinction vector (i.e. the relation between extinction and dust density) is undetermined. In mathematical language, S16 determines a vector, \mathbf{R}_0 , which for a given dust column density, σ , is related to extinction, \mathbf{A} , by

$$\mathbf{A} = \sigma a (\mathbf{R}_0 + b), \quad (4)$$

where a and b are unknown scalar constants. We set the grey component of the reddening vector, b , such that the extinction in the WISE W2 passband is zero, regardless of dust column density. This should bring us close to the correct value of b , as dust optical depth in the W2 passband is small compared to that in optical passbands.

If, instead of assuming that $A_{W2} = 0$, we use the result from Indebetou et al. (2005) that $A_H/A_K = 1.55$ to set the constant b , we arrive at $A_{W2} = 0.12$ mag for $E(r_{P1} - z_{P1}) = 1$ mag. This implies a possible bias in distance of 5 per cent at $E(r_{P1} - z_{P1}) = 1$ mag (similar to $E(B - V) = 1$ mag), and 10 per cent at $E(r_{P1} - z_{P1}) = 2$ mag.

Our method depends trivially on the value of a , since any scaling in the overall extinction vector can be compensated by a reciprocal scaling in the dust column density. The parameter α_{jk} , which represents the amount of dust in distance bin k of sightline j (see Fig. 1), gives the quantity of dust reddening in an arbitrary unit. It is only after multiplying our reddening measure by the extinction vector, \mathbf{R} (see Table 1), that one arrives at a physically meaningful unit – extinction in each passband.

The conversion of our dust map to reddening or extinctions in passbands other than $grizy_{P1}$, J , H or K_S depends on how one extends our extinction vector, \mathbf{R} , beyond these passbands. We set the value of the normalization constant, a , such that $\alpha = 1$ corresponds to a reddening of $E(g_{P1} - r_{P1}) = 0.901$ mag. This has the effect of putting us on a similar scale as the original SFD map and Bayestar15. One may convert our map to $E(B - V)$ by assuming that $E(B - V) = 0.981 E(g_{P1} - r_{P1})$, as found by SF11, implying that $E(B - V) = 0.884 \alpha$. Because we assume a different extinction law to SF11 and Bayestar15, this conversion is not unique, and depends on which PS1 passbands one uses to convert to $E(B - V)$. For example, if one instead uses the relation $E(B - V) = 0.932 E(r_{P1} - z_{P1})$ (SF11), then one finds that $E(B - V) = 0.996 \alpha$. The root of this difference in conversion from α to $E(B - V)$ is that the ratio of $E(g_{P1} - r_{P1})$ to $E(r_{P1} - z_{P1})$ differs between the Fitzpatrick (1999) reddening law assumed in SF11 and the S16-based reddening law used in the present work.

Table 1 gives the components of our adopted extinction vector, which is based on S16. In order to transform values in our Bayestar17 map into extinction in any PS1 or 2MASS passband,




Figure 1. Directed factor graph (Dietz 2010) of the Bayestar model. Unfilled circles represent parameters to be inferred, diamonds represent parameters that are deterministic functions of their inputs, and shaded circles represent observed variables. Constants (such as \mathbf{R}) are not enclosed, while solid squares represent random processes. In the above diagram, the solid square labelled \mathcal{N} represents the measurement process, which introduces Gaussian noise into the observed apparent magnitudes.

Table 1. Extinction vector, \mathbf{R} , adopted in this work.

g_{P1}	r_{P1}	i_{P1}	z_{P1}	y_{P1}	J	H	K_{S}
3.384	2.483	1.838	1.414	1.126	0.650	0.327	0.161

one should multiply our map value by the appropriate component of the extinction vector.

We also use newer PS1 data (see Section 3.1), which requires the creation of new stellar templates, which give the absolute magnitude of a star in the PS1 and 2MASS passbands as a function of luminosity and metallicity, suited to the latest calibration of the PS1 point-source catalogue. These templates were generated according to the same technique described in Green et al. (2014, 2015).

The model described in Fig. 1 does not specify *how* the sky is pixelized into lines of sight. There, the assignment of stars to sightlines is taken as a given. In *Bayestar15* and in this work, we use the HEALPix pixelization scheme (Gorski et al. 2005). In *Bayestar15*, pixel size varied over the sky, and was determined by a heuristic that took into account the observed density of stars. Beginning with large HEALPix pixels ($n_{\text{side}} = 64$, corresponding to an angular scale of $\sim 55'$), we recursively subdivided each pixel until the number of stars fell below a given threshold (given here in Table 2). This threshold was based on the pixel scale, with the number of stars required to trigger a further subdivision increasing as the pixel scale became smaller. The idea behind this scheme is to provide greater angular resolution in areas where there are more stars available to trace the dust column. Across much of the sky, this heuristic works well, allowing us to achieve similar signal-to-noise in regions of the sky with vastly different stellar surface densities. One undesirable outcome of this heuristic, however, is that areas of the sky with particularly dense dust clouds, which block out a significant fraction of the background stars, are pixelized more roughly. Yet these dense clouds contain intricate dust substructure,

Table 2. Pixelization of the sky.

n_{side}	Pixel scale	Max. stars pix^{-1}	Ω (deg^2)	# of pixels
64	$55'$	200	62	74
128	$27'$	250	86	410
256	$14'$	300	10 080	192 156
512	$6.9'$	800	14 179	1080 495
1024	$3.4'$	–	7041	2147 770
total	–	–	31 439	3420 905

which our model (uniform extinction across a sightline, with only white-noise angular substructure) captures poorly. Therefore, in the current work, we modify the pixelization procedure of *Bayestar15* to make the subdivision threshold depend not only on the pixel scale, but also on the SFD estimate of dust reddening.

In detail, we multiply the subdivision thresholds by V -band transparency. If the threshold number of stars for HEALPix $n_{\text{side}} m$ is N_m , then the modified threshold is given by

$$N'_m = 10^{-\frac{2}{3}A_V} N_m, \quad (5)$$

where $A_V = 3.1 E(B - V)_{\text{SFD}}$ is the V -band extinction given by SFD. Here, we use the mean $E(B - V)_{\text{SFD}}$ of the stars in the pixel. This will have the effect of causing greater subdivision in regions with high optical extinction. We limit the suppression of the subdivision threshold so that $N'_m \geq \frac{1}{4} N_m$. As a consequence, the optical transparency term can only cause one additional subdivision. As we show in Section 4.2.2, our new dust map has finer angular resolution than *Bayestar15* in regions of high extinction.

The final two changes that we have made to our method are minor. In our prior on the spatial distribution of stars, we have adjusted the local abundance of halo stars, relative to the local abundance of thin-disc stars. In *Bayestar15*, we had set the local halo

fraction to 0.0006, as indicated by Robin et al. (2003). However, we found that our inferred distribution of stellar distances indicated a greater local halo fraction. We have therefore increased the local halo fraction to 0.003, closer to the value suggested by Jurić et al. (2008). We use the same smooth prior on the distribution of dust as in Bayestar15, with one small modification. As before, our prior on the density of dust in each distance bin of each sightline is lognormal, with a mean value set to trace a smooth disc model, described in detail in section 2.1 of Bayestar15. We found previously that setting a lower limit on the mean of the lognormal distribution in each distance bin improved convergence. We have lowered this floor from $\Delta E(B - V) = e^{-12} \text{mag}$ to $\Delta E(B - V) = e^{-24} \text{mag}$ per distance bin. We have found that this change does not significantly affect convergence, and that it allows us to more rigidly enforce the prior that there is little dust far away from the midplane of the Galaxy.

3 DATA

As in Bayestar15, we use broad-band photometry from two large photometric surveys, Pan-STARRS 1 (PS1) and the Two Micron All-Sky Survey (2MASS).

3.1 Pan-STARRS 1

The Panoramic Survey Telescope and Rapid Response System 1 (Pan-STARRS 1, or PS1) is a 1.8-m optical and near-infrared telescope located on Mount Haleakala, Hawaii (Chambers et al. 2016). The telescope is equipped with the Gigapixel Camera #1 (GPC1), consisting of an array of 60 CCD detectors, each 4800 pixels on a side (Tonry et al. 2006; Onaka et al. 2008; Chambers et al. 2016). From 2010 May to 2014 April, the majority of the observing time was dedicated to a multi-epoch 3π -steradian survey of the sky north of declination $\delta = -30^\circ$ (Chambers et al. 2016, the 3π survey). The 3π survey observed in five passbands, g_{P1} , r_{P1} , i_{P1} , z_{P1} and y_{P1} , similar to those used by SDSS (York et al. 2000), with the most significant difference being the replacement of the Sloan u band with a near-infrared band, y_{P1} . The PS1 filter set spans 400–1000 nm (Stubbs et al. 2010). The images are processed by the PS1 Image Processing Pipeline (IPP) (Magnier et al. 2016a), which performs automatic astrometry and photometry (Magnier et al. 2016b). The internal relative photometric calibration of the data is better than 1 per cent (Chambers et al. 2016; Schlafly et al. 2012). The 3π survey reaches typical single-epoch 5σ depths of 22.0 mag (AB) in g_{P1} , 21.8 mag in r_{P1} , 21.5 mag in i_{P1} , 20.9 mag in z_{P1} , and 19.7 mag in y_{P1} (Chambers et al. 2016). The resulting homogeneous optical and near-infrared coverage of three quarters of the sky makes the PS1 photometry ideal for studies of the distribution of the Galaxy’s dust.

The PS1 Data Release 1 (DR1) occurred in 2016 December. Among other data products, DR1 included the static sky catalogue and stack images from the 3π survey (Flewelling et al. 2016).

As compared to Bayestar15, we use an additional ~ 1.5 yr of data from PS1. The present paper is based on single-epoch data from the PS1 DR1 3π survey. We note that the major advantage of using the additional 1.5 yr of PS1 observations is the more uniform overall coverage. While the slightly deeper limiting magnitudes do allow us to detect 1 per cent more sources overall (with 52.5 per cent of sources now having detections in five or more passbands, versus 49 per cent in Bayestar15), the major gain can likely be attributed to the additional epochs of observation, which reduce photometric uncertainties and systematics, particularly at the faint end. In addi-

Table 3. Source statistics.

	Per cent sources detected in each band	Per cent sources detected in N bands	
g_{P1}	78.9	4	28.9
r_{P1}	98.1	5	52.5
i_{P1}	97.0	6	4.8
z_{P1}	98.1	7	5.1
y_{P1}	93.9	8	8.7
J	18.7	–	–
H	15.6	–	–
K_S	11.8	–	–
806 million sources total.			

tion, Bayestar17 includes the north equatorial pole, which was not included in the data reduction used by Bayestar15.

3.2 Two Micron All Sky Survey

The Two Micron All Sky Survey (2MASS) is a uniform all-sky survey in three near-infrared bandpasses, J , H and K_S (Skrutskie et al. 2006). The survey derives its name from the wavelength range covered by the longest-wavelength band, K_S , which lies in the longest-wavelength atmospheric window not severely affected by background thermal emission (Skrutskie et al. 2006). The survey was conducted from two 1.3-m telescopes, located at Mount Hopkins, Arizona and Cerro Tololo, Chile, in order to provide coverage for both the northern and southern skies, respectively. The focal plane of each telescope was equipped with three 256×256 pixel arrays, with a pixel scale of $2'' \times 2''$. Each field on the sky was covered six times, with dual 51-ms and 1.3-s exposures, achieving a 10σ point-source depth of approximately 15.8, 15.1 and 14.3 mag (Vega) in J , H and K_S , respectively. Calibration of the survey is considered accurate at the 0.02 mag level, with per-source photometric uncertainties for bright sources below 0.03 mag (Skrutskie et al. 2006).

We use the 2MASS ‘high-reliability catalogue’, requiring in addition that there be no contamination/confusion with neighbouring point sources or with galaxies.

3.3 Input catalogue

We match 2MASS to PS1 sources, requiring detection in at least two PS1 passbands, and at least four passbands in total. Our input catalogue contains 806 million sources, divided among 3.42 million sightlines. Over 80 per cent of sources are detected in four or five passbands, with the remaining 20 per cent of sources having detections in six, seven or eight passbands (see Table 3 for more details). After adaptive subdivision of the sky, the number of pixels at each angular scale (or, equivalently, HEALPix n_{side}) is given in Table 2.

4 RESULTS

We massively parallelized our computations across the Harvard Odyssey computing cluster, taking advantage of the independence of each sightline in our model. To check for convergence, we ran four independent Markov Chain Monte Carlo (MCMC) chains for each sightline. The computations took a total of 2.5 million CPU hours, amounting to $2.7 \text{s star}^{-1} \text{chain}^{-1}$. The final product is a 3D map of interstellar reddening, covering three quarters of the sky at typical resolutions ranging from $3.4'$ to $13.7'$.

In Section 4.1, we present maps of both cumulative reddening and differential reddening in discrete distance slices. In Section 4.2.2, we compare our new 3D dust map with our previous map in [Bayestar15](#). In Section 4.2.5, we compare our new 3D dust map with 2D dust maps derived from far-infrared dust emission.

4.1 3π steradian maps of reddening

Fig. 2 shows cumulative reddening across the PS1 footprint, covering the 3π steradians of the sky that lie north of declination $\delta = -30^\circ$. As can be seen, we recover the familiar projected dust structure. Figs 3 to 6 show the differential reddening in discrete distance slices. As we reside in the plane of a disc galaxy, dust extends to the greatest latitudes in the nearest distance slice. In the nearest distance panel, Fig. 3, well-known nearby clouds are visible, such as the Perseus–Taurus–Auriga cloud complex ($150^\circ \lesssim \ell \lesssim 190^\circ$, $-40^\circ \lesssim b \lesssim -10^\circ$), Cepheus ($\ell \approx 110^\circ$, $b \approx 17^\circ$), the ρ Ophiuchi cloud complex ($\ell \approx 350^\circ$, $b \approx 15^\circ$), the Orion nebulae ($\ell \approx 210^\circ$, $b \approx -18^\circ$) and the Aquila Rift ($0^\circ \lesssim \ell \lesssim 30^\circ$, $0^\circ \lesssim b \lesssim 20^\circ$). In subsequent distance slices, distinct features are visible, indicating that we have separated out real dust structures at each distance.

Fig. 7 shows a top-down view of Bayestar17, looking straight down on the Galactic plane, with the Solar system at the centre of the image. Specifically, the figure shows the mean reddening per kiloparsec within 50 pc of the $b = 0^\circ$ plane.

4.2 Comparison with previous maps

There are two different classes of dust maps with which we would like to compare our results: 3D dust maps based on stellar photometry, and 2D dust maps based on the optical depth of dust emission in the far infrared. Here, we pick one map of each type to compare against. First, in Section 4.2.2, we compare our new 3D dust map with the previous version, [Bayestar15](#). Then, in Section 4.2.3, we compare our individual stellar reddening estimates against reddenings derived from SDSS spectra. Next, in Section 4.2.4, we compare our map with the 3D dust map of [Sale14](#), which covers the northern Galactic plane. Finally, in Section 4.2.5, we compare our projected map with the 2D dust FIR optical-depth-based map from [Planck14](#).

4.2.1 Units of comparison

When comparing reddening or extinction maps that make different assumptions about the wavelength–extinction relation, one has to be careful about defining what units are to be used in the comparison. For example, assume that in some arbitrary colour, $X - Y$, the reddening estimates given by maps A and B are related by a simple multiplicative factor:

$$E(X - Y)_A = \gamma E(X - Y)_B, \quad (6)$$

where γ is some constant. In a new colour, $X' - Y'$, the relation between the two maps will be

$$E(X' - Y')_A = \gamma' E(X' - Y')_B, \quad (7)$$

where

$$\gamma' = \left[\frac{E(X' - Y')_A}{E(X - Y)_A} \right] \bigg/ \left[\frac{E(X' - Y')_B}{E(X - Y)_B} \right]. \quad (8)$$

If maps A and B assume different wavelength–extinction relations, then the slope of the linear relation between the two maps depends on the colour chosen for the comparison.

In order to compare our new map to [Bayestar15](#), we use the $r_{P1} - z_{P1}$ colour. We choose this colour because r_{P1} and z_{P1} span the mid-range of wavelengths covered by PS1. The vast majority of stars that we use in constructing our 3D dust map are observed in r_{P1} , i_{P1} and z_{P1} . For $R_V = 3.1$, $E(r_{P1} - z_{P1}) \approx 1.07 E(B - V)$, based on the Fitzpatrick (1999) reddening law, as computed by [SF11](#).

When comparing to [Planck14](#), we convert [Planck14](#)'s $E(B - V)$ estimates to $E(g_{P1} - r_{P1})$, because g_{P1} and r_{P1} span a similar range of wavelengths as B and V . The conversion between $E(g_{P1} - r_{P1})$ and $E(B - V)$ is therefore relatively insensitive to changes in the reddening law. One complication is that if the wavelength–extinction relation deviates significantly from our assumed [S16](#) model, then different colours will tend to drive our inferred stellar reddenings to different values, and our resulting stellar reddening estimates will be a compromise between the values preferred by the different colours. In our comparisons with [Planck14](#), we use the relation $E(g_{P1} - r_{P1}) = 1.02 E(B - V)$, likewise derived using an $R_V = 3.1$ Fitzpatrick (1999) reddening law, as computed by [SF11](#).

One may use this latter relation to convert Bayestar17 to $E(B - V)$, with the caveat that the exact conversion may vary across the sky with R_V . Since with our assumed reddening vector, given in Table 1, $E(g_{P1} - r_{P1}) = 0.901 \alpha$, the above relation between $E(g_{P1} - r_{P1})$ and $E(B - V)$ implies that $E(B - V) = 0.88 \alpha$, where α is the extinction parameter that our map reports, defined in Section 2.1.

4.2.2 Comparison with Bayestar15

As discussed in Section 2.2, the major differences in the way in which our new 3D dust map was compiled, versus the [Bayestar15](#) dust map, are:

- (i) the use of an additional 1.5 yr of PS1 photometry,
- (ii) the use of a new extinction vector, and
- (iii) finer angular resolution in areas of increased dust opacity.

To convert the [Bayestar15](#) map into $E(r_{P1} - z_{P1})$, we use the $R_V = 3.1$ extinction vector given by [SF11](#), as this is the extinction vector that was assumed when constructing [Bayestar15](#). To convert Bayestar17 into $E(r_{P1} - z_{P1})$, we use the extinction coefficients given in Table 1, based on the work of [S16](#). In Fig. 8, we plot the difference in integrated reddening between the new and old dust maps across the entire PS1 footprint.

At high Galactic latitudes ($|b| > 45^\circ$), the new map, Bayestar17, infers ~ 0.014 mag greater integrated $r_{P1} - z_{P1}$ reddening than [Bayestar15](#), with a scatter of less than 0.015 mag (see Fig. 9b). Deep in the plane of the Galaxy ($|b| < 5^\circ$), Bayestar17 also has a slight offset relative to the old map (of ~ 0.03 mag), with a scatter between the two maps of less than 0.1 mag, out to a reddening of $E(r_{P1} - z_{P1}) \approx 1.5$ mag (see Fig. 9d). The overall offset between the two maps (between ~ 0.014 mag and ~ 0.03 mag) may be due to a small overall offset in the colour zero-point of the updated stellar templates used in Bayestar17, with the newer templates being slightly bluer than the old ones used by [Bayestar15](#). As can be seen in Fig. 9(b), at reddenings below $E(r_{P1} - z_{P1}) \sim 0.03$ mag, [Bayestar15](#) predicts less reddening than Bayestar17. This is consistent with the stellar templates used by the [Bayestar15](#) map being slightly too red. Combined with the strictly positive prior on dust reddening, this would cause [Bayestar15](#) to infer zero reddening when true dust reddening is below a critical threshold.

In the midplane of the Galaxy, Bayestar17 appears to extend to greater dust optical depths than the old map, [Bayestar15](#).




Figure 2. Cumulative reddening out to the maximum distance in the 3D dust map, in magnitudes of $E(r_{P1} - z_{P1})$. The map uses a Galactic Mollweide projection, with the $\ell = 0^\circ$ meridian rotated to the right of the map. The map covers declinations north of -30° (the PS1 3 π survey footprint). Regions shaded blue lie south of declination -30° , and are therefore not covered by this map.




Figure 3. Cumulative reddening out to 500 pc, in magnitudes of $E(r_{P1} - z_{P1})$.

This is apparent in Fig. 9(d), where at SFD reddenings beyond $E(r_{P1} - z_{P1}) \sim 2$ mag, Bayestar17 infers more reddening than Bayestar15. This is likely because of improvements to the extinction vector, which result in a better fit to highly extinguished stars. As fewer stars are rejected at high extinctions for poor model fit, Bayestar17 is able to probe more deeply into the Galactic plane. The increased depth may also be due in part to the slightly deeper coverage provided by the additional 1.5 yr of PS1 photometry.

As can be seen in Fig. 8, at about 15° off the plane of the Galaxy, Bayestar17 tends to infer slightly less dust than the old map. This may be due to the changes to the line-of-sight prior described in Section 2.2. Specifically, the new prior more strenuously requires minimal reddening far off the plane of the Galaxy. As can be seen

in Fig. 9(c), the old map tends to infer a slight increase in reddening at a distance of $\mu \sim 11$ mag in this region of the sky. Because the new prior favours less dust far off the midplane of the Galaxy, Bayestar17 does not infer this increase in reddening, and therefore infers ~ 0.02 mag less dust reddening in $E(r_{P1} - z_{P1})$.

Due to our changes to the pixelization scheme and the increased number of sources in the final PS1 data release, Bayestar17 generally traces the structure of dense dust clouds with finer angular resolution. An example of this is given in Fig. 10, which shows the regions around the ρ Ophiuchi cloud complex (top panels) and the Perseus cloud complex (bottom panels). Due to the finer angular resolution of Bayestar17, the edges of filamentary structures are clearly visible in the difference image.




Figure 4. Cumulative reddening between 500 pc and 1 kpc, in magnitudes of $E(r_{P1} - z_{P1})$.




Figure 5. Cumulative reddening between 1 kpc and 2 kpc, in magnitudes of $E(r_{P1} - z_{P1})$.

4.2.3 Comparison with SF11

Schlafly & Finkbeiner (2011, SF11) measured reddenings of stars with both SDSS spectra and photometry. The SDSS Stellar Parameters Pipeline (Lee et al. 2008, SSPP) uses stellar spectra to estimate stellar temperature, metallicity and surface gravity. SF11 calculated synthetic SDSS photometry by applying the SDSS transmission curves to MARCS stellar atmospheric models (Gustafsson et al. 2008). By comparison of synthetic and observed stellar colours in relatively dust-free regions of the sky, SF11 calculated an empirical correction to the synthetic SDSS colours, arriving at an accurate mapping from intrinsic stellar parameters to SDSS colours. By comparing these model colours with observed SDSS stellar colours, SF11 obtained reddening estimates for a quarter of a million stars. A distinct advantage of the SF11 reddenings is that they do not assume any particular reddening law. By contrast, in Bayestar17, we set the vector \mathbf{R} , which relates extinction in different passbands, at the outset, as described in Section 2.1.

We have repeated the SF11 analysis to obtain reddening estimates in PS1 passbands for the same set of stars with SDSS spectra. We use

these reddening estimates to validate the stellar reddenings inferred by the Bayestar17 map. In the process of producing the Bayestar17 map, we obtain two reddening estimates for each star:

(i) **‘raw’ stellar inferences:** For each star, we pre-compute a likelihood and prior term, informed by the star’s photometry and the distribution of stars within the Galaxy. These individual stellar inferences (which we here term the ‘raw’ inferences) are then used to infer the line-of-sight reddening, as described in Green et al. (2014, 2015).

(ii) **‘reweighted’ stellar inferences:** It is then possible to refine the individual stellar distance and reddening inferences, by forcing the individual stars to be consistent with the inferred line-of-sight distance-versus-reddening relation. We term these refined stellar parameter inferences the ‘reweighted’ inferences. This empirical Bayesian procedure is described in detail in Section 2.4 of Bayestar15.

In Fig. 11, we compare the reddening estimates derived from SSPP with both our ‘raw’ and ‘reweighted’ stellar reddenings. We




Figure 6. Cumulative reddening between 2 kpc and 5 kpc, in magnitudes of $E(r_{p1} - z_{p1})$.




Figure 7. A bird's-eye view of our new dust map, showing reddening per kiloparsec in the plane of the Galaxy. At each location in the plane of the Galaxy, mean reddening per kiloparsec within 50 pc of the $b = 0^\circ$ plane is plotted. The Sun is located at the centre of plot, and the Galactic centre lies off the plot to the right. The region without data lies below declination $\delta = -30^\circ$. The ‘fingers-of-God’ effect, by which clouds are elongated along the radial axis (from the perspective of the Sun), is due to the fact that angular positions of dust clouds are much more precisely determined than their distances. At a distance of 1 kpc, a $6.8'$ -pixel spans a transverse distance of 2 pc, while with our distance resolution of 25 per cent, it extends 250 pc in the radial direction.




Figure 8. An all-sky map of the residuals between Bayestar17 and Bayestar15, in magnitudes of $E(r_{P1} - z_{P1})$. Both maps have been integrated to infinite distance. In each pixel, a random sample from each map is drawn. Positive values (blue) indicate that Bayestar17 infers greater cumulative reddening. Grey corresponds to areas with no PS1 data. The hole at $l \approx 120^\circ$, $b \approx 30^\circ$ corresponds to the equatorial north pole, which had not yet been reduced in the version of the PS1 photometry used by Bayestar15.




Figure 9. Residuals between Bayestar17 and Bayestar15, in magnitudes of $E(r_{P1} - z_{P1})$. **Top left:** As a function of SFD $E(r_{P1} - z_{P1})$ reddening, off the plane of the Galaxy. For each bin of SFD reddening, we show the histogram of reddening residuals vertically. For both 3D dust maps, we choose random samples of cumulative reddening to compare. The blue lines show the 16th, 50th and 84th percentiles of the residuals. **Top right:** Same as top left, but selecting only the high-Galactic-latitude sky ($|b| > 45^\circ$). An overall offset of +0.014 mag is found. **Bottom right:** As top left and top right, but selecting instead only the Galactic plane ($|b| < 5^\circ$). A similar overall reddening offset is found as at high Galactic latitudes, but at large reddening, Bayestar17 finds more reddening than the old map, Bayestar15. This indicates that Bayestar17 extends to greater dust optical depths. **Bottom left:** Reddening residuals as a function of distance modulus, in a region of the sky where Bayestar17 finds less cumulative reddening than Bayestar15. The discrepancy is due to an increase in reddening in Bayestar15 at distance modulus $\mu \sim 11$ mag, corresponding to a height of ~ 400 pc above the plane of the Galaxy. This increase in reddening in Bayestar15 is likely spurious, as it occurs several dust scale heights above the plane of the Galaxy.

obtain good agreement with the SF11 reddening estimates. As expected, the reweighted reddening estimates match the SF11 reddening estimates more closely than the raw estimates. At low reddenings, $E(B - V) \lesssim 0.1$ mag, our individual-star raw inferences are greater than SF11, due to our prior on reddening being non-negative.

Our inferred reddenings match SF11 most closely in the $i_{P1} - z_{P1}$ colour, while Bayestar17 predicts slightly higher reddenings than SF11 in $g_{P1} - r_{P1}$, and slightly lower reddenings in $z_{P1} - y_{P1}$. These trends are likely due to variations in the extinction law. The extinction vector \mathbf{R} assumed in this work represents the mean extinction




Figure 10. A close-in view of the residuals between the new 3D dust map and the [Bayestar15](#) 3D dust map, in the vicinity of the ρ Ophiuchi cloud complex (**top row**) and the Perseus cloud complex (**bottom row**). In the top row, reddening has been integrated to infinite distance, while in the bottom row, reddening has been integrated to 800 pc. As our dust maps are probabilistic, each panel shows median quantities. The new dust map (**left column**) has finer angular resolution than the [Bayestar15](#) dust map (**centre column**). The finer resolution is especially visible in the top row, where sharp filamentary structures in ρ Ophiuchi produce gradients in the residual map.

vector for APOGEE stars used in [S16](#), corresponding roughly to $R_V = 3.3$. If we hold the Bayestar17 $r_{p1} - z_{p1}$ reddenings fixed, while varying the reddenings in the other colour combinations to match an $R_V = 3.1$ extinction law from [S16](#), we approximately match [SF11](#) reddening estimates in all colour combinations equally well. This is evidence for the mean foreground dust extinction law being somewhat steeper for the SDSS stars used by [SF11](#) (which reside at high Galactic latitudes) than the APOGEE stars used by [S16](#) (which reside in the Galactic midplane). [Schlafly et al. \(2017\)](#) found that nearby dust, within ~ 1 kpc, has significantly lower R_V (corresponding to a steeper fall-off of extinction with wavelength)

than more distant dust in the Milky Way. One consequence of this is that the high-Galactic-latitude sky, which is dominated by nearby dust, should have lower average R_V than the Galactic plane, consistent with our findings in this work. These large-scale differences in R_V underline the importance of tracing extinction-law variations in future three-dimensional dust maps.

4.2.4 Comparison with Sale14

[Sale14](#) maps the northern Galactic plane ($|b| < 5^\circ$, $30^\circ < \ell < 215^\circ$) using a method that simultaneously infers stellar distances and




Figure 11. Correlation between Bayestar17 reddenings for individual stars and reddenings derived from SDSS spectroscopy, using the method developed by SF11. The panels on the left use ‘raw’ samples of stellar reddening, informed only by the photometry of each star in isolation. As such, these reddenings do not take into account the inferred line-of-sight reddening distribution in Bayestar17. The panels on the right use reweighted samples of stellar reddening, which are informed by the line-of-sight reddening distribution, using the empirical Bayesian procedure developed in Section 2.4 of Bayestar15. The x -axis corresponds to the SFD $E(B - V)$ reddening.

types, as well as the line-of-sight dust distribution. The Sale14 map is based on stellar photometry from IPHAS (Drew et al. 2005). Sale14 reports extinction in terms of A_0 , the extinction at 5495 Å. In order to compare this extinction measure with $E(r_{P1} - z_{P1})$, we first convert A_0 to V -band extinction, using the median relation found in Sale14, namely $A_0 = 1.003A_V$. Then, we use the $R_V = 3.1$ coefficients from table 6 of SF11, obtaining the conversion $E(r_{P1} - z_{P1}) = 0.35A_0$. Note that this relation depends on the assumed extinction law. Fig. 13 shows the correlation between cumulative reddening to 2 kpc in Bayestar17 and Sale14, finding good agreement between the two maps. Fig. 12 shows the difference in cumulative reddening, out to five distances, between Bayestar17 and Sale14. The two maps agree well at 2 kpc and 3 kpc, although within the nearest kiloparsec, some clouds are inferred to be closer in Sale14 than in Bayestar17. This can be seen especially in the residual map to 500 pc, where Sale14 generally infers a greater dust column than Bayestar17.

4.2.5 Comparison with Planck14

Planck14 fits a simple dust-emission model to all-sky far-infrared Planck and IRAS data. The dust is treated as a modified blackbody, described by an optical depth, temperature and spectral index. Both the dust optical depth at 353 GHz, τ_{353} , and the integrated radiance, \mathcal{R} , can be used to trace dust reddening. We will hereafter refer to Planck optical-depth-based reddenings as ‘ τ_{353} ’.

Planck14 gives a linear calibration between optical depth at 353 GHz and $E(B - V)$ derived from SDSS quasar colours in regions of the high-Galactic-latitude sky with low $H I$ column density. As noted in Section 4.2.1, we convert these values to $E(g_{P1} - r_{P1})$

reddening using the relation $E(g_{P1} - r_{P1}) = 1.02E(B - V)$, allowing a direct comparison with the $E(g_{P1} - r_{P1})$ reddening reported by Bayestar17. At Galactic latitudes of $|b| > 60^\circ$, Bayestar17 agrees well with Planck14, with a constant offset of 0.01 mag in $E(r_{P1} - z_{P1})$, as can be seen in Fig. 14. However, at intermediate Galactic latitudes, $15^\circ < |b| < 60^\circ$, we find lower reddening than Planck14. This may be due to variation in the extinction curve, which would cause the ratio of dust FIR optical depth to optical/NIR reddening to vary. This interpretation is supported by the fact that we find agreement in the scale of reddening at high Galactic latitudes, where Planck14’s FIR optical depth-to-reddening relation is calibrated, but discrepancies at lower Galactic latitudes. In the remainder of this section, we therefore compare Bayestar17 to $0.75 \times \tau_{353}$, removing the linear trend between τ_{353} and Bayestar17 seen at intermediate Galactic latitudes.

Fig. 15 shows the difference in $E(g_{P1} - r_{P1})$ dust reddening between our new 3D map, integrated to infinite distance, and $0.75 \times \tau_{353}$. In low-reddening regions of the sky, the two maps agree well, once the linear trend noted above is removed. Maps based solely on stellar photometry, as ours is, cannot trace dust beyond the farthest observable stars. The limiting distance of our map is therefore dependent on the line-of-sight extinction. Thus, in the Galactic plane, where the dust column is largest, the Planck map sees more total dust than does our 3D dust map.

One salient feature in Fig. 15 that deserves note is the extended region towards the Galactic centre where Bayestar17 (like Bayestar15 before it) infers greater reddening than Planck14. This region is too extended to line up well with the Galactic bulge, but it does align well with nearby dust that lies within $\lesssim 500$ pc. This suggests that nearby dust in the region $45^\circ \lesssim \ell \lesssim 0^\circ$ has different FIR emission and/or optical/NIR extinction properties than dust elsewhere. Our method is more sensitive to changes in stellar colours, while Planck14 is more sensitive to changes in thermal dust emission. Therefore, either a steepening of the extinction spectrum (i.e. greater reddening per unit extinction, corresponding to lower R_V), greater FIR emissivity, or systematically overestimated dust temperatures would create the observed residuals. We see similar residuals when comparing with SFD, indicating that they are not due to any peculiar feature of Planck14.

Fig. 16(a) shows the correlation in inferred integrated reddening between Bayestar17 and the Planck14 τ_{353} dust map. Out of the plane of the Galaxy, the two maps agree to within ~ 10 percent after τ_{353} is rescaled by 0.75. However, the exact level of agreement varies over the sky, as shown in Fig. 17, which shows the correlation between our 3D map and the Planck optical-depth-based 2D dust map in four regions of the sky. As can be seen in Fig. 17, the slope of the rescaling that would be required to bring τ_{353} into alignment with Bayestar17 is different from one region of the sky to another, which could be indicative of systematic changes in the extinction curve (e.g. varying R_V). Such variations are not implausible, given the large-scale variations in R_V found by Schlafly et al. (2017).

Fig. 16(b) shows the correlation in integrated reddening between the old 3D dust map, Bayestar15, and the Planck14 dust map. Overall, Bayestar15 infers 15 percent less $E(g_{P1} - r_{P1})$ reddening than Planck14. This is slightly different from the scale difference between Bayestar17 and Planck, due to the different extinction vectors assumed by Bayestar15 and Bayestar17. At low reddening, Bayestar15 infers less reddening than Planck out to a reddening of ~ 0.05 mag in $E(g_{P1} - r_{P1})$. Bayestar15 tends to infer zero reddening when the true reddening is below a few hundredths of a magnitude. This is again consistent with the stellar templates used in Bayestar15 being slightly too red, as discussed




Figure 12. A comparison of Bayestar17 with Sale14, which covers the northern Galactic plane. The left-hand panels show Bayestar17 over this footprint, integrated out to different distances. The right-hand panel shows the difference between Bayestar17 and Sale14 out to these same distances. Positive values (blue) indicate that Bayestar17 infers greater cumulative reddening. In each pixel, a random sample of Bayestar17 and Sale14 is drawn.




Figure 13. Comparison of Bayestar17 with Sale14, integrated out to 2 kpc. For each bin of SFD reddening, we show the histogram of reddening residuals. All units are in magnitudes of $E(r_{P1} - z_{P1})$.




Figure 14. Comparison of Bayestar17 with the Planck14 τ_{353} dust map at high Galactic latitudes. For each bin of SFD reddening, we show the histogram of reddening residuals. All units are in magnitudes of $E(gp_1 - r_{P1})$. At these high Galactic latitudes and low reddenings, our map predicts 0.01 mag greater reddening than τ_{353} , and the slope of our map versus τ_{353} is close to unity.

in Section 4.2.2. This effect is not seen when comparing the new 3D dust map, Bayestar17, with the Planck14 dust map (see Fig. 16a), indicating that this low-reddening systematic effect is largely resolved in Bayestar17.

5 DISCUSSION

This map is an update on the 3D map released by Bayestar15. The advantages of our new map, Bayestar17, are that it includes an additional year-and-a-half of PS1 data, a more accurate extinction vector (S16), and finer angular resolution in heavily extinguished regions of the Galaxy. Bayestar17 recovers largely the same qualitative features as the previous map, Bayestar15, but probes to slightly greater depths. With distance projected out, Bayestar17 correlates better, especially at low reddenings, with the 2D Planck FIR optical-depth-based dust map.

For extra-Galactic astronomy, where only the integrated extinction or reddening is typically of interest, dust maps that are based directly on stellar photometry provide a valuable complement to FIR emission-based maps. The two methods have different types of systematics. Emission-based maps depend on a detailed modelling of the temperature, optical depth, and the shape of the emission spectrum – the latter possibly based on a physical model of dust properties, as in Planck Collaboration (2016), or on a simple empirical model, as in SFD, Planck14 and Meisner & Finkbeiner (2015). By contrast, dust maps based on stellar photometry more directly measure reddening, but depend on accurate modelling of stellar spectral energy distributions and assumptions about the shape of the dust extinction spectrum. As shown in Section 4.2.5, at low extinctions (where star-based maps can still observe background stars), these two methods generally have a scatter of ~ 10 per cent, although the slope of the relation between the two types of maps can vary by ~ 25 per cent across different regions of the sky. Variations in residuals across the sky between these two types of dust map are potentially an indication of variation in the relation between the extinction and emission properties of dust. Such variations are expected, as dust grain composition and size are known to vary (for an overview of interstellar dust properties, see Draine 2003), although the large spatial extent of these variations is surprising. S16 measures one side of this variation – the variation in the dust extinction vector – by measuring the variation in the colours of stars of known spectral types. Schlafly et al. (2017) combine R_V measurements for individual stars with the three-dimensional distribution of dust (from Bayestar15) to map variation in dust R_V in three dimensions across the Galaxy. Unmodelled variation in the dust extinction vector is one source of residuals between our 3D dust map and emission-based dust maps, but incompletely mod-




Figure 15. An all-sky map of the residuals between our new 3D dust map, Bayestar17, and the Planck14 optical-depth-based 2D dust map, in magnitudes of $E(g_{p1} - r_{p1})$. In order to reduce the 3D dust map to two dimensions, it is integrated out to infinite distance. As the 3D dust map is probabilistic, we draw a random sample of cumulative dust reddening in each pixel. After the removal of an overall ~ 25 per cent difference in scale, the two dust maps have good agreement outside of the Galactic midplane. Because the far-infrared dust optical depth is small compared to the optical/near-infrared optical depth, the Planck dust map traces the dust to a greater column density in the plane of the Galaxy.




Figure 16. **Left:** Reddening residuals between Bayestar17 and the Planck14 τ_{353} 2D dust map, as a function of reddening, as measured by SFD. All reddenings are in magnitudes of $E(g_{p1} - r_{p1})$. For each bin of SFD reddening, we show the histogram of reddening residuals. The small panel to the right shows the overall histogram of residuals, combining all SFD reddening bins. We restrict the comparison to Galactic latitudes of $|b| > 15^\circ$. For Bayestar17, we choose random samples of cumulative reddening. The blue lines show the 16th, 50th and 84th percentiles of the residuals. There is an overall 25 per cent difference in scale between the two maps. **Right:** Reddening residuals between the Bayestar15 3D dust map and τ_{353} . There is an overall 15 per cent difference in scale between the two maps.

elled variation in dust-emission properties must also contribute to the residuals. In addition, FIR zodiacal light (from dust grains in the Solar system) and contamination from large-scale structure (due to dust emission in distant galaxies) introduce systematics into far-infrared emission-based dust maps, which are not present in maps based on stellar colours.

Our 3D dust map currently assumes a universal dust extinction law (see Section 2.1) with $R_V \approx 3.3$. Allowing the dust extinction spectrum to vary is a priority for constructing a more accurate 3D dust map. One way of doing this would be to infer not only a dust density in each voxel, but also a dust R_V . In order to avoid producing an underconstrained model, one should take advantage of spatial smoothness in both dust density and R_V , imposing a prior that correlates dust properties in nearby voxels. A number of methods have been proposed to impose a smoothness

condition on the 3D dust density field. Sale & Magorrian (2014) and Rezaei et al. (2017) lay out differing methods of imposing smoothness on a 3D dust map by treating the dust density field as a Gaussian process.

It is also possible to impose smoothness on the dust density field as a post-processing step on a map constructed from independent sightlines, assuming that a sufficient number of samples have been saved for each sightline. A selection of one sample from each sightline may be regarded as a sample from the entire map. By applying a new, joint prior linking nearby sightlines, one may reweight samples of the full map. This process produces a set of realizations of the full map in which neighbouring sightlines are consistent with one another, in that dust density varies smoothly with angle. For a map with n_{pix} angular pixels and n_{samples} stored samples of the distance–reddening relation in each angular pixel, the total number




Figure 17. Residuals between Bayestar17 and Planck14 τ_{353} , in magnitudes of $E(g_{P1} - r_{P1})$, as a function of SFD $E(g_{P1} - r_{P1})$ reddening. Each panel shows a different quarter of the sky, illustrating that the correlation between our 3D dust map and the Planck dust map varies over the sky.

of realizations of the full map is given by

$$n_{\text{realizations}} = (n_{\text{samples}})^{n_{\text{pix}}} . \quad (9)$$

For our map, $n_{\text{pix}} = 3.42 \times 10^6$ and $n_{\text{samples}} = 500$, yielding $n_{\text{realizations}} \approx 10^{107}$. Clearly, reweighting the posterior probability of every realization of the full map is not feasible. However, this problem lends itself to the types of strategies commonly pursued to sample from the 2D Ising model of ferromagnetism. Such strategies can yield a representative set of realizations of the full map. We leave more detailed discussion of this method to future work.

Incorporating new types of data sets will also improve the accuracy of 3D dust maps. In particular, parallaxes measured by the ESA space telescope Gaia (Lindegren et al. 1994) will provide future maps with tight priors on the distances to a billion stars, effectively removing distance as a fitting parameter for a large subset of stars. Distance determinations and stellar types provided by Gaia will also aid in the construction of more accurate stellar photometric templates. Finally, Gaia’s spectrophotometry can be used to infer stellar type and reddening, in much the same way as we currently use PS1 and 2MASS photometry.

We intend to extend 3D reddening mapping to cover the entire sky, and to that end, we have imaged the portion of the Galactic plane visible only from the Southern hemisphere with the Dark Energy Camera (DECam). The resulting five-band optical/NIR survey delivers high-quality photometry of approximately two billion point sources, and is described in Schlafly et al. (2018). As various other projects fill out DECam coverage of the remainder of the Southern sky, a high-quality, 4π -steradian, 3D map of Galactic reddening will become possible.

6 CONCLUSIONS

We have produced a new 3D map of interstellar dust reddening, based on stellar photometry from PS1 and 2MASS. The new map,

Bayestar17, covers the 3π steradians north of declination $\delta = -30^\circ$. Bayestar17 is not a direct map of $E(B - V)$, as it is based on stellar colours in the PS1 and 2MASS passbands. However, it may be converted to $E(B - V)$, as explained in Section 4.2.1. Bayestar17 is compiled using a nearly identical method to Bayestar15, but with the addition of an extra 1.5 yr of PS1 photometry, an updated extinction vector from S16, and finer angular resolution in regions of high extinction. Bayestar17 probes somewhat more deeply than the old map, Bayestar15, in the plane of the Milky Way. In low-extinction regions of the sky, Bayestar17 shows better agreement with 2D FIR emission-based dust maps, such as Planck14. Above the plane of the Galaxy, the average scatter between Bayestar17 and Planck14 is ~ 10 per cent, although the slope between the two maps varies across the sky by ~ 25 per cent.

Three-dimensional dust maps based on stellar photometry have a number of advantages over FIR dust-emission-based maps, including the ability to trace dust in 3D, and the fact that they more directly trace the quantity of interest – dust extinction. Maps based on stellar photometry will not only be of use in tracing extinction in the plane of the Galaxy, where the distance-dependence of extinction is crucial, but can also provide a complementary measurement of dust reddening for extra-Galactic astronomy. Since the systematic uncertainties in stellar photometric reddenings are very different from the types of systematic effects in emission-based maps, one can expect the two types of measurements to have uncorrelated errors. In particular, stellar photometric reddenings do not suffer from contamination from zodiacal light or large-scale structure. Maps based on stellar photometry also have the potential to trace changes in the extinction curve (see, for example, Schlafly et al. 2017). Producing a 3D dust map that traces spatial variation in both dust density and the extinction curve, taking into account the smoothness of these quantities in space, will be an important development in dust mapping efforts.

Our new 3D dust map can be accessed at <http://argonaut.sky.maps.info>, or by its digital object identifier (DOI): [10.7910/DVN/LCYHJG](https://doi.org/10.7910/DVN/LCYHJG). In addition, the Python package `dustmaps` provides an interface for Bayestar17, Bayestar15, SFD and other three- and two-dimensional dust maps.

ACKNOWLEDGEMENTS

The Pan-STARRS1 Surveys (PS1) have been made possible through contributions of the Institute for Astronomy, the University of Hawaii, the Pan-STARRS Project Office, the Max Planck Society and its participating institutes, the Max Planck Institute for Astronomy, Heidelberg, and the Max Planck Institute for Extraterrestrial Physics, Garching, the Johns Hopkins University, Durham University, the University of Edinburgh, Queen's University Belfast, the Harvard-Smithsonian Center for Astrophysics, the Las Cumbres Observatory Global Telescope Network Incorporated, the National Central University of Taiwan, the Space Telescope Science Institute, the National Aeronautics and Space Administration under grant No. NNX08AR22G issued through the Planetary Science Division of the NASA Science Mission Directorate, the National Science Foundation under grant No. AST-1238877, the University of Maryland, and Eötvös Loránd University (ELTE). This publication makes use of data products from the 2MASS, which is a joint project of the University of Massachusetts and the Infrared Processing and Analysis Center/California Institute of Technology, funded by the National Aeronautics and Space Administration and the National Science Foundation. The computations in this paper were run on the Odyssey cluster supported by the FAS Science Division Research Computing Group at Harvard University. GG and DF are supported by NSF grant AST-1312891. ES acknowledges support for this work provided by NASA through Hubble Fellowship grant HST-HF2-51367.001-A awarded by the Space Telescope Science Institute, which is operated by the Association of Universities for Research in Astronomy, Inc., for NASA, under contract NAS 5-26555.

REFERENCES

Berry M. et al., 2012, *ApJ*, 757, 166
 Burstein D., Heiles C., 1978a, *ApJ*, 19, L69 (BH)
 Burstein D., Heiles C., 1978b, *ApJ*, 225, 40 (BH)
 Burstein D., Heiles C., 1982, *AJ*, 87, 1165 (BH)
 Cardelli J. A., Clayton G. C., Mathis J. S., 1989, *ApJ*, 345, 245
 Chambers K. C. et al., 2016, preprint ([arXiv:1612.05560](https://arxiv.org/abs/1612.05560))
 Chen B.-Q. et al., 2014, *MNRAS*, 443, 1192
 Dietz L., 2010, Technical report, Directed Factor Graph Notation for Generative Models. Max Planck Institute for Informatics, Saarbrücken, Germany
 Draine B., 2003, *ARA&A*, 41, 241
 Drew J. E. et al., 2005, *MNRAS*, 362, 753
 Fitzpatrick E. L., 1999, *PASP*, 111, 63

Flewelling H. A. et al., 2016
 Gorski K. M., Hivon E., Banday A. J., Wandelt B. D., Hansen F. K., Reinecke M., Bartelmann M., 2005, *ApJ*, 622, 759
 Green G. M., 2017, 3D Dust Map from Green et al. (2017), Harvard Data-verse, V2. Available at: <https://doi.org/10.7910/DVN/LCYHJG>
 Green G. M., et al., 2014, *ApJ*, 783, 114
 Green G. M. et al., 2015, *ApJ*, 810, 25 (Bayestar15)
 Gustafsson B., Edvardsson B., Eriksson K., Jørgensen U. G., Nordlund Å., Plez B., 2008, *A&A*, 486, 951
 Indebetouw R. et al., 2005, *ApJ*, 619, 931
 Jurić M. et al., 2008, *ApJ*, 673, 864
 Lallement R., Vergely J.-L., Valette B., Puspitarini L., Eyer L., Casagrande L., 2014, *A&A*, 561, A91
 Lee Y. S. et al., 2008, *AJ*, 136, 2022
 Lindegren L. et al., 1994, in Ealey M. A., Merkle F., eds, Conference Series Vol. 2200, Amplitude and Intensity Spatial Interferometry II. SPIE Proceedings, Kailua, Kona, HI, p 599. Available at: <http://spiedigitallibrary.org/proceeding.aspx?doi=10.1117/12.177278>
 Magnier E. A. et al., 2016a
 Magnier E. A. et al., 2016b
 Majewski S. R. et al., 2017, *AJ*, 154, 94
 Marshall D. J., Robin A. C., Reylé C., Schultheis M., Picaud S., 2006, *A&A*, 453, 635
 Meisner A. M., Finkbeiner D. P., 2015, *ApJ*, 798, 88
 Onaka P., Tonry J. L., Isani S., Lee A., Uyeshiro R., Rae C., Robertson L., Ching G., 2008, in Ground-based and Airborne Instrumentation for Astronomy II, 70140D. SPIE Proceedings, Marseille, France, p 1
 Planck Collaboration, 2014, *A&A*, 571, A11 (Planck14)
 Planck Collaboration, 2016, *A&A*, 586, A132
 Rezaei Kh. S., Bailer-Jones C. A. L., Hanson R. J., Fouesneau M., 2017, *A&A*, 598, A125,
 Robin A. C., Reylé C., Derrière S., Picaud S., 2003, *A&A*, 409, 523
 Sale S. E., Magorrian J., 2014, *MNRAS*, 445, 256
 Sale S. E. et al., 2014, *MNRAS*, 443, 2907 (Sale14)
 Schlafly E. F., Finkbeiner D. P., 2011, *ApJ*, 737, 103 (SF11)
 Schlafly E. F., Peek J. E. G., Finkbeiner D. P., Green G. M., 2017, *ApJ*, 838, 36
 Schlafly E. F. et al., 2012, *ApJ*, 756, 158
 Schlafly E. F. et al., 2016, *ApJ*, 821, 78 (S16)
 Schlafly E. F., et al., 2018, The Astrophysical Journal Supplement Series, 234, 39
 Schlegel D. J., Finkbeiner D. P., Davis M., 1998, *ApJ*, 500, 525 (SFD)
 Skrutskie M. F. et al., 2006, *AJ*, 131, 1163
 Stubbs C. W., Doherty P., Cramer C., Narayan G., Brown Y. J., Lykke K. R., Woodward J. T., Tonry J. L., 2010, *ApJS*, 191, 376
 Tonry J., Onaka P., Luppino G., Isani S., 2006, in The Advanced Maui Optical and Space Surveillance Technologies Conference. p. E47
 Trumpler R. J., 1930, *PASP*, 42, 267
 Wright E. L. et al., 2010, *AJ*, 140, 1868
 York D. G. et al., 2000, *AJ*, 120, 1579
 Yuan H.-B., Liu X.-W., Xiang M.-S., 2013, *MNRAS*, 13, 2188

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.